

SCHEDULE OF QUANTITY

Job No. 1

Estimated cost- 37519

Time Allowed-1 Month

Bidders Name & Address : _____

Assistant Engineer
Municipal Corporation
Mandi (H.P.)

Name of Work :-Repair of damaged retaining wall near Tehsildar Residence Mangwain W. No. 5 Mandi H.P.

S. No.	Item of work	Qty.	Unit.	Rate (in figures)	Amount
1	Demolishing stone rubble masonry built in cement mortar manually/by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge:	1.22	Com		
2	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement:6 course sand: 12 graded stone aggregate 20mm nominal size upto plinth level with CM 1:6 (1 cement: 5 course sand) in retaining wall etc	3.59	Com		
3	taking down existing collapsible gate of size 2.50mx2.80m and refixing the same at other place at the time of construction of stone pillars	1	Job		
4	Earth work in excavation by mechanical means (Hydraulic excavator/manual means in foundation, trenches or drains (not exceeding 1.5 mtr in with or 10 sqm on plan, including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 mtr, any kind of soil.	1.42	Com		

Assistant Engineer
Municipal Corporation
Mandi (H.P.)

5	Providing and laying in position cement concrete of grade 1:4:8 (1 cement :4 coarse sand: 8 stone aggregate 40mm nominal size) excluding cost of centering and shuttering - all work upto plinth level.	0.3	Com		
6	15mm cement plaster on the rough side of single or half brick wall of mix 1:4 (1 cement: 4 fine sand	19.51	Sqm		
	Total				


 Assistant Engineer
 Municipal Corporation
 Mandi (H.P.)