

JOB NO. -8

Bidders Name & Address _____

Dated _____

Assistant Engineer
Municipal Corporation
Mandi (H.P.) Form-6

**MUNICIPAL CORPORATION MANDI
NOTICE INVITING TENDER**

1. Items rate tenders are hereby invited on behalf of the Commissioner Municipal corporation mandi for the work: **Construction of Municipal toilet at Chobata in W.No. 12 MC Mandi (H.P.)**
2. The estimated Cost of Rs. 139884/-
3. Contractor documents consisting of detail plans complete specifications. The scheduled of quantities of the various clause of work to be done and the set of conditions of contract to be complied with the persons whose tender may be accepted which will also be found printed in the form of tender. The tender form can be downloaded from the website www.municipalcorporationmandi.in well before date of opening of bid. Tender form cost on **Rs. 350** payment (Non refundable) through DD in favors of Commissioner Municipal Corporation Mandi
4. The site for the work can be inspected on any working day.
5. Tender which should always be placed in sealed covers with the name of work written on the envelop will be received by this office up to 12.00 A.M. and will be opened by him on his office on the same day at **12.30 P.M on 31-1-2026.**
6. Tender are to be on PWD from No. 7/8 and time allowed for carrying out of the work will be 2 month to be reckoned from the 15th days after the date of written orders to commence of work.
7. The contractors should quote in figures as well as in words the rate & amount tendered by him the amount for each item should be worked out and the requisite total given.
8. When a contractor sign a tender in any Indian language to the percentage above or below of the tenders amount in the case of P.W.D. from-7 and the total amount tendered in the case of PWD from-8 and scheduled also be written in the same language. In the case of illiterate contractors the rates or the amounts tendered should be attested by a witness.
9. Issue of tender form will be stopped 3 hours before the date 7 time fixed for opening the tenders.
10. Earnest money amounting to **Rs. 2800** (Unless exempted) must accompany each tenders in the shape of National Saving Certificate/Fixed deposit receipts in any Post Office and bank in HP duly pledged in the name of the Commissioner Municipal Corporation Mandi and each tender is to be in sealed cover subscribed tender for above work and addressed to the Commissioner Municipal Corporation Mandi
11. The tenders those contractors who do not deposit the earnest money in the prescribed manners will summarily be rejected.
12. The acceptance of the tender will rest with Municipal Corporation Mandi, who does not bind himself to accept the lowest tender and reserves to himself the authority to reject any or all of the tenders conditions are not fulfilled on are incomplete in any respect are liable to be rejection.
13. Canvassing in connection with tenders strictly prohibited and the tender by the contractor who resort of conversing will be rejection.
14. All rate shall quoted on the form of the tender alone.
15. Item rate tender containing percentage below above will be summarily rejected. However then a tenderer voluntarily offers rebate for payments within a stipulated period, this may be considered.
16. On acceptance of the tender the same of the accredited representative (s) of the contractor who would be responsible for taking instruction from the Engineer-in-charge shall be communicated to the Engineer.
17. Special care should be taken to write the rates in figures as well as in words and the amounts in figures only in such a way that interpolation is not possible. The total amount should be written both in figures and in words. In case figures, words (Rs.) should be written before the figures proceed and the words 'paisa')

- should be written at the end, unless the rate in whole Rupees and followed by the word 'only' it should invariably by up to two decimal places.
18. The Commissioner of Municipal Corporation Mandi does not bind himself to accept the lowest or any tender and reserve to himself the right of accepting the whole and any part of the tender and the tender shall be bound to perform the same at the rates quoted.
 19. GST or any other tax on material in respect of this contract shall be payable by the contractor and the Government will not entertain any claim whatsoever in this respect.
 20. The contractor must produce income tax clearing certificate and GST 3R before the tender can be sold to him.
 21. The Contractor shall not be permitted to tender for the work in Municipal Corporation Mandi responsible for award and execution of contract in which his near relative is posted as Section officer or as officer in any capacity between the grades of Executive Engineer and Assistant Engineer (Both inclusive). He shall also intimate the name of person who are working with him and who are near relative to any gazetted officer in the MC MANDI. Any breach of this condition by the contractor would render him liable to be removed from the approved list of the contractor of his department.
 22. The contractor shall give a list of non gazetted MC Mandi employee related to him. No. Engineer of gazetted rank or other gazetted officer employed in Engineering or Administrative duties in an Engineering department of the Government of Himachal Pradesh of allowed to work as a contractor for a period of two years of his employees found at any time to be such person who had not obtained the previous permission of the Government of Himachal Pradesh as aforesaid before submission of the tender or engagement in the contractors service.
 23. Tender for works in Himachal Pradesh shall remain open for acceptance for a period of 75 days from date of opening of tender.
 24. The tenders for the work shall not be witnessed by a contractor to contractor who self/themselves/has/have tendered or who may tenders for the same work. Failure to observe this condition would render the contractor tendering as well as witnessing the tender liable of summary.
 25. While quoting the rate in the schedule of quantities the word 'ONLY' should be written cost following the amount and it should not be written in the next line.
 26. In case the original tender of the signature of the event letter's refusal to sign, his earnest money shall be forfeited.
 27. The contractor shall submit a list of the work which are in hand/progress.
 28. Overwriting in the tender is strictly and forbidden and correction if any should be intimated, tender containing doubtful figure shall be rejected.
 29. If the rate quoted by the two or more bidder match at L1, then successful bidder will be declared through length of experience and average last three year turnover.
 30. The tender shall sign each page of the tender form.
 31. Earnest money of L1 & L2 shall be retained for a period of 30 days.
 32. The undersigned reserve the right to reject any or all tenders without assigning any reason.
 33. The TDS on income tax and GST will be deducted as per rule. It shall also be ensured at the time of making bills that EPF has been deposited by the contractor as per the ACT.
 34. The labourcess @1% will be deducted from the gross amount of the work done of the contractor.
 35. Fair wages shall be applicable as notified by the HP Govt and applicable on the date of opening of the tender as amended by the H.P Govt time to time.
 36. It will be mandatory to give employment to the skilled/unskilled persons as per notification No UD-F(4)-2/2020 dated Shimla 171002 the Mukhya Mantri Shahri Ajeevika Guarantee Yojna (MMSAGY) (According to minimum wages act of H.P Govt) for detail information log on to <http://ud.hp.in>

Signature of Contractor.
(With full Address)

Assistant Engineer,
Municipal Corporation Mandi.

For and on behalf of Commissioner
Municipal Corporation Mandi.

SCHEDULE OF QUANTITY

Job No. 8

Estimate Cost: 139884.00

Earnest Money: 2800.00

Time Allowed: 2 month

Tender Form Cost: 350.00

Name & address of Bidder-----

Assistant Engineer
Municipal Corporation
Mandi (H.P.)

Name of Work:- Construction of municipal toilet at chobata in W.No. 12 MC Mandi (H.P.).

S. No.	Item of work	Qty.	Unit.	Rate (in figures)	Rates (In words)	Amount
1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	2.24	cum			
2	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	0.32	cum			
3	Excavation in earth work and disposal of all excavated earth upto a lead of 20metres and lift upto 1.50metres, disposed earth to be levelled and neatly dressed. Pick Work	1.01	cum			
4	Disposal of moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved municipal dumping ground for lead upto 10 km for all lifts, complete as per directions of Engineer-in-charge. Note - item to be applicable in urban areas having directions for restricted hours for movement/ plying of load carrying motor vehicle of 3.5 cum or more.	3.58	cum			
5	Boulder filling dry hand packed tightly under floors	0.28	cum			
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering-All work upto plinth level. 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	0.23	cum			

7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand)	2.79	cum			
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size).	0.46	cum			
9	Centering and shuttering including strutting, propping etc. and removal of form for all heights: Suspended floors, roofs, landings, balconies and access platform	4.92	sqm			
10	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sq.m including pointing the joints with white cement and matching pigments etc., complete.	2.25	Sqm			
11	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	21.17	sqm			
12	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	3.75	sqm			
13	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete: 40 mm thick with 20 mm nominal size stone aggregate	4.00	sqm			

14	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6 mm angle iron and 3 mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer: Using M.S. angels 40x40x6 mm for diagonal braces	1.58	sqm			
15	Steel work welded in built up sections / framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In Gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	50.95	Kg			
16	Providing and fixing fly proof stainless steel grade 304 wire gauge, to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia. 0.50 mm all complete. With 12 mm mild steel U beading	0.54	sqm			
17	Providing and fixing CERA (Cat No. : S4020112) CAPRIANA Snow White Colour urinal, with fittings, standard size C.P. brass flush pipe, spreaders with unions and clamps (all in C.P. brass) with waste fitting as per IS : 2556, C.I. trap with outlet grating and other couplings in C.P. brass, including painting of fittings and cutting and making good the walls and floors wherever required	1.00	each			
18	Providing and fixing P.V.C. waste pipe for sink or wash basin, urinal Including P.V.C. waste fittings complete. Flexible pipe 32mm dia	1.00	each			
19	Providing and fixing CERA (Cat No. : F2013201) Fountain Angle Cock with wall flange of approved quality	1.00	each			
20	Providing & Fixing SS Grating of approved quality : Circular Type: 125 mm nominal dia with 25 mm waste hole	2.00	each			
21	Providing and fixing uplasticised PVC connection pipe with brass unions : 45 cm length: 15 mm nominal bore	1.00	each			
22	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, Including cost of cutting and making good the walls and floors : 100 mm inlet and 75 mm outlet : Sand cast iron S&S as per IS: 3989	2.00	each			

23	Providing and fixing on walls or laid in floor 75mm diameter unplasticised Rigid PVC pipe single socketed conforming to IS 13592 Type A including jointing with seal ring	3.00	Rmt			
24	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer In Charge. Concealed work, including cutting chases and making good the walls etc. 15 mm nominal outer dia Pipes	6.00	Rmt			
25	Providing and fixing on walls or laid in floor unplasticised Rigid PVC moulded fitting/accessories Shoe (Plain): 75 mm Shoe for PVC pipes conforming to IS 13592 Type A including jointing with seal ring	5.00	each			
26	Providing and fixing on walls or laid in floor unplasticised Rigid PVC moulded fitting/accessories (Bend 87.5 degree 75mm) for PVC pipes conforming to IS 13592 Type A including jointing with seal ring	5.00	each			
27	Providing and fixing on walls unplasticised Rigid PVC pipe clips 75mm of approved designed to PVC pipes by means of 50x50x50mm hard wood plugs, screwed with MS Screws of required length, including cutting brickwork and fixing in cement mortar 1:4 (1 cement : 4 coarse sand) and making good the wall etc complete	5.00	each			
28	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 75 mm diameter	3.50	Rmt			
29	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete: 15 mm nominal bore	2.00	each			
30	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 :15 mm nominal bore	1.00	each			
31	Providing and fixing PTMT Ball cock of approved quality, colour and make complete with Epoxy coated aluminium rod with L.P. / H.P.H.D. plastic ball. 20 mm nominal bore, 120 mm long, weighing not less than 198 gms	1.00	each			

32	Providing and placing polyethylene Water Storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	500.00	Litre			
33	Painting with synthetic enamel paint of approved brand and manufacture (Asian/Berger paint or its equivalent) of required colour to give an even shade : two or more coats on new work	7.01	sqm			
34	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm	3.75	sqm			
35	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto & above plinth level:Thermo-Mechanically Treated bars of grade Fe-500D or more.	50.60	kg			
36	Providing & fixing Display board of Size 3' x 2' (minimum) indicating Name of work, Name of head, Estimated Cost, Date of Award, Date of start, Date of completion & Expenditure of work on site of work at prominent place.	1.00	each			
	Total					


 Assistant Engineer
 Municipal Corporation
 Mandi (H.P.)