

SCHEDUL OF QUANTITY (NIQ)

Bidder Name & Address -----

Assistant Engineer
Municipal Corporation
Mandi (H.P.)

Job No. 06

Estimate Cost: 40024.00

Time Allowed: 2 month

Name of Work:- Providing PVC pipe to prevent seepage of dirty water flowing near H. No. 377/1/11 W. No. 13.

S. No.	Item of work	Qty.	Unit.	Rate (in figures)	Rates (In words)	Amount
1	Providing and fixing on walls or laid in floor 110mm diameter unplasticised Rigid PVC pipe single socketed conforming to IS 13592 Type A including jointing with seal ring	52.00	RM			
2	Providing and fixing on walls or laid in floor unplasticised Rigid PVC moulded fitting/accessories (Single Tee with door 110x110x110mm) for PVC pipes conforming to IS 13592 Type A including jointing with seal ring	1.00	Each			
3	Providing and fixing on walls or laid in floor unplasticised Rigid PVC moulded fitting/accessories (Bend 87 degree 110mm) for PVC pipes conforming to IS 13592 Type A including jointing with seal ring	8.00	Each			
4	Providing and fixing on walls unplasticised Rigid PVC pipe clips 110mm of approved designed to PVC pipes by means of 50mm screws and PVC rawl plug and making good the wall etc complete	16.00	Each			
5	Providing and fixing on walls or laid in floor unplasticised Rigid PVC moulded fitting/accessories (Single Tee without door 110x110x110mm) for PVC pipes conforming to IS 13592 Type A including jointing with seal ring	2.00	Each			
6	Providing and fixing on walls or laid in floor unplasticised Rigid PVC moulded fitting/accessories (Coupler- socket 110mm) for PVC pipes conforming to IS 13592 Type A including jointing with seal ring	9.00	Each			
	Total					

Assistant Engineer
Municipal Corporation
Mandi (H.P.)