

SCHEDUL OF QUANTITY (NIQ)

Bidder Name & Address -----

Assistant Engineer
Municipal Corporation
Mandi (H.P.)

Job No. 05

Estimate Cost: 35484.00

Time Allowed: 2 month

Name of Work:- Providing and fixing water tank with MS Stand near Ambedkar Park in MC Mandi Ward no. 10 (Suhra)

S. No.	Item of work	Qty.	Unit.	Rate (in figures)	Rates (In words)	Amount
1	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 15 mm dia nominal bore	12.00	Rmt			
2	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 :15 mm nominal bore	1.00	each			
3	Providing and fixing PTMT Ball cock of approved quality, colour and make complete with Epoxy coated aluminium rod with L.P. / H.P.H.D. plastic ball. 20 mm nominal bore, 120 mm long, weighing not less than 198 gms	1.00	each			
4	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete: 15 mm nominal bore	1.00	each			
5	Providing and placing polyethylene Water Storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	500.00	Litre			
6	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) : 15 mm nominal bore	3.00	each			
7	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All Kinds of Soil	0.16	Cum			

8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size)	0.16	cum			
9	Steel work welded in built up sections / framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In Gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	151.63	Kg			
	Total					


 Assistant Engineer
 Municipal Corporation
 Mandi (H.P.)