

SCHEDULE OF QUANTITY

Job No. 2

Estimated cost- 13081.00

Bidders Name & Address : _____

Assistant Engineer
Municipal Corporation
Mandi (H.P.)

Name of Work :- Providing & Fixing MS Bollards near MC entrance gate in Ward No. 10					
S. No.	Item of work	Qty.	Unit.	Rate (in figures)	Amount
1	Demolishing cement concrete/bituminous macadam/pavers manually/by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge, nominal concrete 1:3:6 or richer mix(i/c equivalent design mix)	0.19	Cum		
2	Providing and laying in position cement concrete in position of grade 1:2:4 (1 cement: 2 Coarse Sand: 4 graded stone aggregate 20mm nominal size, excluding cost of centering and shuttering - All work up to plinth level	0.19	Cum		
3	Structural steel work in single section, fixed with or without connecting plate, in in position and applying a priming coat of approved steel primer all complete	94.15	Kg.		

4	Painting with synthetic enamel paint of approved brand and manufactures (Asian/Berger paint or its equivalent) of required colour to give an even shade on new work wooden or steel surfaces with two or more coat as required	2.87	Sqm		
5	Disposal of moorum/building rubbish/malica/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved mōnicipal dumping ground for lead upto 10 km for all lifts, complete as per directions of Engineer-in-charge. Note - item to be applicable in urban areas having directions for restricted hours for movernent/plying of load carrying motor vehicle of 3.5 cum or more.	0.19	Cum		
	Total				


 Assistant Engineer
 Municipal Corporation
 Mandi (H.P.)