Issued	
1001100	10:-

Dated

nicipal Corporation

## MUNICIPAL CORPORATION

## NOTICE INVITING TENDER

- 1. Items rate tenders are hereby invited on behalf of the Commissioner Municipal corporation mandi for the work: Site development for proposed park at Panjethi at W. No. 7 MC Mandi H.P
- 2. The estimated Cost of Rs. 171959/-
- 3. Contractor documents consisting of detail plans complete specifications. The scheduled of quantities of the various clause of work to be done and the set of conditions of contract to be complied with the persons whose tender may be accepted which will also be found printed in the form of tender. The tender form can be downloaded from the website www.municipalcorporationmandi.in well before date of opening of bid. Tender form cost on Rs. 350 payment (Non refundable) through DD in favors of Commissioner Municipal Corporation Mandi
- The site for the work can be inspected on any working day.
- Tender which should always be placed in sealed covers with the name of work written on the envelop will be received by this office up to 12.00 A.M. and will be opened by him on his office on the same day at 12.30 P.M on 20-9-2025.
- Tender are to be on PWD from No. 7/8 and time allowed for carrying out of the work will be 2 month to be reckoned from the 15th days after the date of written orders to commence of work.
- The contractors should quote in figures as well as in words the rate & amount tendered by him the amount for each item should be worked out and the requisite total given.
- 8. When a contractor sign a tender in any Indian language to the percentage above or below of the tenders amount in the case of P.W.D. from-7 and the total amount tendered in the case of PWD from-8 and scheduled also be written in the same language. In the case of illiterate contractors the rates or the amounts tendered should be attested by a witness.
- Issue of tender form will be stopped 3 hours before the date 7 time fixed for opening the tenders.
- 10. Earnest money amounting to Rs. 3500 (Unless exempted) must accompany each tenders in the shape of National Saving Certificate/Fixed deposit receipts in any Post Office and bank in HP duly pledged in the name of the Commissioner Municipal Corporation Mandi and each tender is to be in sealed cover subscribed tender for above work and addressed to the Commissioner Municipal Corporation Mandi
- 11. The tenders those contractors who do not deposit the earnest money in the prescribed manners will
- 12. The acceptance of the tender will rest with Municipal Corporation Mandi, who does not bind himself to accept the lowest tender and reserves to himself the authority to reject any or all of the tenders conditions are not fulfilled on are incomplete in any respect are liable to be rejection.
- 13. Canvassing in connection with tenders strictly prohibited and the tender by the contractor who resort of conversing will be rejection.
- 14. All rate shall quoted on the form of the tender alone.
- 15. Item rate tender containing percentage below above will be summarily rejected. However then a tenderer voluntarily offers rebate for payments within a stipulated period, this may be considered.
- 16. On acceptance of the tender the same of the accredited representative (s) of the contractor who would be responsible for taking instruction from the Engineer-in-charge shall be communicated to the Engineer.
- 17. Special care should be taken to write the rates in figures as well as in words and the amounts in figures only in such a way that interpolation is not possible. The total amount should be written both in figures and in words. In case figures, words (Rs.) should be written before the figures proceed and the words 'paisa') should be written at the end, unless the rate in whole Rupees and followed by the word 'only' it should invariably by up to two decimal places.
- 18. The Commissioner of Municipal Corporation Mandi does not bind himself to accept the lowest or any tender and reserve to himself the right of accepting the whole and any part of the tender and the tender shall be bound to perform the same at the rats quoted.

- 19. GST or any other tax on material in respect of this contract shall be payable by the contract and the Government will not entertain any claim what so ever in this respect.
- 20. The contractor must produce income tax clearing certificate and GST 3R before the tender can be sold to
- 21. The Contractor shall not be permitted to tender for the work in Municipal corporation Mandi responsible for award and execution of contract in which his near relative is posted as Section officer or as officer in any capacity between the grades of Executive Engineer and Assistant engineer (Both inclusive). He shall also intimate the name of person who are working with him and who are near relative to any gazetted officer in the MC MANDI. Any breach of this condition by the contractor would render him liable to be remove from the approved list of the contractor of his department.
- 22. The contractor shall give a list of non gazetted MC Mandi employee related to him. No. Engineer of gazetted rank or other gazetted officer employed in Engineering or Administrative duties in an Engineering department of the Government of Himachal Pradesh of allowed to work as a contract for a period of two years of his employees found at any time to be such person who had not obtained the previous permission of the Government of Himachal Pradesh as aforesaid before submission of the tender or engagement in the contractors service.
- 23. Tender for works in Himachal Pradesh shall remain open for acceptance for a period of 75 days from date of opening of tender.
- 24. The tenders for the work shall not be witnessed by a contractor to contactor who self/themselves/has/have tendered or who may tenders for the same work. Failure to observe this condition would tender for the contractor tendering as well as witnessing the tender liable of summary.
- 25. While quoting the rate in the schedule of quantities the worked 'ONLY' should be written cost following the amount and it should not be written in the next line.
- 26. In case the original tender of the signature of the event letter's refusal to sign, his earnest money shall be
- 27. The contractor shall submit a list of the work which are in hand/progress.
- 28. Overwriting in the tender is strictly and forbidden and correction if any should be intimated, tender containing doubtful figure shall be rejected.
- 29. The tender shall sign each page of the tender form.
- 30. Earnest money of L1 &L2 shall be retained for a period of 30 days.
- 31. The undersigned reserve the right to reject any or all tenders without assigning any reason.
- 32. The TDS on income tax and GST will be deducted as per rule. It shall also be ensured at the time of making bills that EPF has been deposited by the contractor as per the ACT.
- 33. The labourcess @1% will be deducted from the gross amount of the work done of the contractor.
- 34. Fair wages shall be applicable as notified by the HP Govt and applicable on the date of opening of the tender as amended by the H.P Govt time to time.
- 35. It will be mandatory to give employment to the skilled/unskilled persons as per notification No UD-F(4)-2/2020 dated Shimla 171002 the Mukhya Mantri Shahri Ajeevika Guarantee Yojna (MMSAGY) (According to minimum wages act of H.P Govt) for detail information log on to http://ud.hp.in

Signature of Contractor. (With full Address)

ngineer, Municipal Corporation Mandi.

For and on behalf of Commissioner Municipal Corporation Mandi.

Estimated cost- 171959 Earnest Money-3500 Time Allowed-2 Month Tender Form Cost-350

Date:\_\_\_\_\_

Downloaded	PN
lection to .	

Assistan Engineer
Municipal Corporation

Item of work	Qty.	Unit.	Rate (in figures)	Amount
Excavation in foundation, trenches etc. in earth work, lift up to 1.5 Meters stacking the excavated soil not more than 3 Meters clear from the edge of the excavation and then returning the stacked soil in 15CM cm layers, when required in to plinths sides of foundations etc., consolidating each deposited layer by ramming and watering and then disposing of all Surplus excavated earth as directed with in a lead of 20 Meters.	11.34	Cum	3-1-1-1	
Providing and laying cement conc. In retaining wall, return walls, walls (any thickness) including attached pilaster, column, piers, abutmentpillares post, struts, butterses, string or lacing course, parapets, coping bed block anchor blocks, plain window sill, fillets, sunken floor etc. up to floor five IvI, excluding the cost of centeringshuttering and finising 1:4:8(1 cement: 4Course sand):8graded stone aggregate stone aggregate 40mm nominal size)				
	Excavation in foundation, trenches etc. in earth work, lift up to 1.5 Meters stacking the excavated soil not more than 3 Meters clear from the edge of the excavation and then returning the stacked soil in 15CM cm layers, when required in to plinths sides of foundations etc., consolidatingeach deposited layer by ramming and watering and then disposing of all Surplus excavated earth as directed with in a lead of 20 Meters.  Providing and laying cement conc. In retaining wall, return walls, walls (any thickness) including attached pilaster, column, piers, abutmentpillares post, struts, butterses, string or lacing course, parapets, coping bed block anchor blocks, plain window sill, fillets, sunken floor etc. up to floor five lvl, excluding the cost of centeringshuttering and finising 1:4:8(1 cement: 4Course sand):8graded stone	Excavation in foundation, trenches etc. in earth work, lift up to 1.5 Meters stacking the excavated soil not more than 3 Meters clear from the edge of the excavation and then returning the stacked soil in 15CM cm layers, when required in to plinths sides of foundations etc., consolidatingeach deposited layer by ramming and watering and then disposing of all Surplus excavated earth as directed with in a lead of 20 Meters.  Providing and laying cement conc. In retaining wall, return walls, walls (any thickness) including attached pilaster, column, piers, abutmentpillares post, struts, butterses, string or lacing course, parapets, coping bed block anchor blocks, plain window sill, fillets, sunken floor etc. up to floor five IvI, excluding the cost of centeringshuttering and finising 1:4:8(1 cement: 4Course sand):8graded stone	Excavation in foundation, trenches etc. in earth work, lift up to 1.5 Meters stacking the excavated soil not more than 3 Meters clear from the edge of the excavation and then returning the stacked soil in 15CM cm layers, when required in to plinths sides of foundations etc., consolidatingeach deposited layer by ramming and watering and then disposing of all Surplus excavated earth as directed with in a lead of 20 Meters.  Providing and laying cement conc. In retaining wall, return walls, walls (any thickness) including attached pilaster, column, piers, abutmentpillares post, struts ,butterses, string or lacing course, parapets, coping bed block anchor blocks, plain window sill, fillets, sunken floor etc. up to floor five lvl, excluding the cost of centeringshuttering and finising 1:4:8(1 cement: 4Course sand):8graded stone	Excavation in foundation, trenches etc. in earth work, lift up to 1.5 Meters stacking the excavated soil not more than 3 Meters clear from the edge of the excavation and then returning the stacked soil in 15CM cm layers, when required in to plinths sides of foundations etc., consolidatingeach deposited layer by ramming and watering and then disposing of all Surplus excavated earth as directed with in a lead of 20 Meters.  Providing and laying cement conc. In retaining wall, return walls, walls (any thickness) including attached pilaster, column, piers, abutmentpillares post, struts ,butterses, string or lacing course, parapets, coping bed block anchor blocks, plain window sill, fillets, sunken floor etc. up to floor five lvl, excluding the cost of centeringshuttering and finising 1:4:8(1 cement: 4Course sand):8graded stone

				_	
	Centering and shuttering including strutting, proppingetc and removal of form work for Retainningwalls, returnwalls, walls (any thickness) including attached plaster butteress plinth and strings course fillets kerbs and steps etc.				
3		31.90	Sqm		
	Excavating, supplying and filling of local earth (including royalty) by				
	mechanical transport upto a lead of 5km also including ramming and watering of the				
	earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc.				
4	complete.	57.24	Cum		
	Providing & Fixed Display Board Of Size 3'-0"X2'-0" (Minimum) Indicating				
	Name OF Work, Name Of Head, Estimated Cost, Date Of Award, Date of Start, Date				
5	Of Completion And Expenditure Of Work On Site Of Work At Promonent Place	1	No.		
	Total				

Assistant the new Manager River Box