

SCHEDUL OF QUANTITY (NIQ)

Job No. 01

Bidder Name & Address

Assistant Engineer
Municipal Corporation
Mandi (H.P.)

Estimate Cost :- 35523

Name of Work:- Repair & maintenance of path & C/o drain near H/O Sh. Sanjay Kumar in MC Mandi W.No. 10

S. No.	Item of work	Qty.	Unit.	Rate (in figures)	Rates (In words)	Amount
1	Excavation in earth work and disposal of all excavated earth upto a lead of 20metres and lift upto 1.50metres, disposed earth to be levelled and neatly dressed. Pick Work	2.53	cum			
2	Providing and laying half cut 150 mm R.C.C pipe with stiff mixture of cement mortar in the proportion of 1:2 (1cement : 2 fine sand)	15.00	Rmt			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering-All work upto plinth level. 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	0.51	cum			
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering-All work upto plinth level- 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	2.03	cum			
5	Centering and shuttering including strutting, proppingetc. and removal of form for :Retaining walls, return walls, walls(any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc.	9.00	sqm			
6	Providing & fixing Display board of Size 3' x 2' (minimum) indicating Name of work, Name of head, Estimated Cost, Date of Award, Date of start, Date of completion & Expenditure of work on site of work at prominent place.	1.00	each			
	Total					

Assistant Engineer
Municipal Corporation
Mandi (H.P.)