## **SCHEDUL OF QUANTITY (NIQ)**

Job	NI.	^-
100	IVO.	u

Name of Work:- Repairs to damaged MS Sheet ceiling of rain shelter near Valmiki Mandir in Ward No:10jiMandi)

S. No.	Item of work	Qty.	Unit.	Rate (in	Rates (In	Amount
				figures)	words)	
1	Providing and fixing MS BP Sheet 1.66mm to 2.00mm thick in eaves	5.04	Sqm			
	board/facia/soffits/ceiling including cutting, fixing and welding to steel roof					
	members and applying a coat of red lead primer complete as per the instructions					
	of Engineer-in-charge (Base members of steel work shall be measured & paid					
	seperately)					
2	Painting with synthetic enamel paint of approved brand and	5.04	Sgm	+		
	manufactures(Asian/Berger paint or its equivalent) of required colour to give an					
	even shade on new work wooden or steel surfaces with two or more coat as					
	Total					
				1		

Assistant Engineer Municipal Corporation Mandi (H.P.)