

SCHEDULE OF QUANTITY

Bidders Name & Address :

Assistant Engineer
Municipal Corporation
Mandi (H.P.)

Name of Work :Repair to plaster, MS railing etc in Jawahar Park at Khaliar, Ward No 1, Mandi.

S. No.	Item of work	Qty.	Unit.	Rate (in figures)	Amount
1	Steel work welded in built up sections/framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc as required in grating, frames, guard bar, ladder, railing, brackets, gates and similar works	80.95	Kg		
2	Painting with synthetic enamel paint of approved brand and manufactures(Asian/Berger paint or its equivalent) of required colour to give an even shade on new work wooden or steel surfaces with two or more coat as required	5	Sqm		
3	Painting with synthetic enamel paint of approved brand and manufactures(Asian/Berger paint or its equivalent) of required colour to give an even shade on old work wooden or steel surfaces with one or more coat as required	40	Sqm		
4	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead	24.2	Sqm		
5	12 mm thick Cement plaster of mix 1:4 (1 cement : 4 fine sand)	24.2	Sqm		
6	Finishing walls with water proofing cement paint of required shade on new work (two or more coats applied @ 3.84 Kg/10 Sqm).	24.2	Sqm		
7	Finishing walls with water proofing cement paint of required shade on old work (one or more coats applied @ 2.20 Kg/10 Sqm) complete.	34.73	Sqm		

8	Providing and laying in position cement concrete in pillars, coping, bed blocks etc, upto floor five level of grade 1:2:4 (1 cement : 2 Coarse Sand : 4 graded stone aggregate 20mm nominal size, excluding cost of centering and shuttering and finishing.	0.16	Cum		
	TOTAL				

Assistant Engineer
Municipal Corporation
Mandi (H.P.)