

SCHEDULE OF QUANTITY

Job No. 1

Estimated cost- 37717.00

Time Allowed-1 Month


Assistant Engineer
Municipal Corporation
Mandi (H.P.)

Bidders Name & Address : _____

Name of Work :- Removal of debris & muck from nalla near H/o Smt. Champa in MC Mandi W. No. 9 (Ph-II)

S. No.	Item of work	Qty.	Unit.	Rate (in figures)	Amount
1	Demolishing R.C.C. work manually means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge. Damaged/ broken RCC wall.	12	Cum		
2	Earth work in excavation by mechanical means (Hydraulic xcavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
3	For all kind of soil	21.6	Cum		
4	Ordinary Rock	15	Cum		
	Total				


Assistant Engineer
Municipal Corporation
Mandi (H.P.)