

SCHEDUL OF QUANTITY (NIQ)

Job No. 03

Bidder Name & Address _____

Assistant Engineer
Municipal Corporation
Mandi (H.P.)

Estimate Cost: 22481.00

Time Allowed: 2 month

Name of Work:- Repair of chamber near H/O Sh. Prakash chand in W.No. 10 MC Mandi.

S. No.	Item of work	Qty.	Unit.	Rate (in figures)	Rates (In words)	Amount
1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand)	11.88	sqm			
2	Steel work welded in built up sections / framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In Gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	100.46	Kg			
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.39	cum			
	Total					

Assistant Engineer
Municipal Corporation
Mandi (H.P.)