

# SCHEDULE OF QUANTITY

**Job No. 1**

**Estimated cost- 17318.00**

**Bidders Name & Address :** \_\_\_\_\_

Assistant Engineer  
Municipal Corporation  
Mandi (H.P.)

**Name of Work :- Repair of chamber and providing MS Jala near Ravidass Gurudwara at Khaliyar W. No. 1 Mandi**

S. No.	Item of work	Qty.	Unit.	Rate (in figures)	Amount
1	Demolishing cement concrete manually/by mechanical means term of workposal of material within 50 metres lead as per direction of Engineer-in-charge, nominal concrete 1:3:6 or richer mix(i/c equivalent design mix)	0.38	Cum		
2	Providing and laying in position cement concrete of grade 1:3:6 (1 cement: 3 Coarse Sand : 6 graded stone aggregate 20mm nominal size, excluding cost of centering shuttering All work up to plinth level	0.68	Cum		
3	Centering and shuttering including strutting, propping etc and removal of form for foundations, footing, bases of columns, etc for mass and shuttering	2.7	Sqm		

	Steel work welded in built up sections/framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc as required in grating, frames, guard bar, ladder, railing, brackets, gates and 4 similar works	77.1	Kg.		
	Providing and fixing mild steel heavy duty purpose made hinges of size 65x 60mmx5mm thick welded 5	3	Nos		
	Total				

  
 Assistant Engineer  
 Municipal Corporation  
 Mandi (H.P.)