

SCHEDUL OF QUANTITY (NIQ)

Bidder Name & Address -----

Assistant Engineer
Municipal Corporation
Mandi (H.P.)

Job No. 04

Estimate Cost: 37327.00

Time Allowed: 2 month

Name of Work:- Providing & fixing, repair of MS Grating near H/O Sh. Pawan kumar, Babla tea stall & Moti bazar in W.No. 10 MC Mandi (H.P.).						
S. No.	Item of work	Qty.	Unit.	Rate (in figures)	Rates (In words)	Amount
1	Excavation in earth work and disposal of all excavated earth upto a lead of 20metres and lift upto 1.50metres, disposed earth to be levelled and neatly dressed. Pick Work	0.29	cum			
2	Steel work welded in built up sections / framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In Gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	234.27	Kg			
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.29	cum			
	Total					

Assistant Engineer
Municipal Corporation
Mandi (H.P.)