

SCHEDULE OF QUANTITY

Job No. 5

Estimated cost- 14747.00

Bidders Name & Address : _____

Assistant Engineer
Municipal Corporation
Mandi (H.P.)

Name of Work :- R/M of drain near H/o Hement Vaidya & Sh. Jitender Behl MC W. No. 11 Mandi H.P.					
S. No.	Item of work	Qty.	Unit.	Rate (in figures)	Amount
1	Dismantling C.I. or asbestos/cement rain water pipe/half cut channel with fittings and clamps including stacking the material within 50 metres lead:	25	Rm		
2	Removal of slips/slush in all kinds of soil (including saturated soil but excluding boulders and rocky portion requiring blasting upto a distance of 20 metres dosposing of un-serviceable materials, stacking	2	Cum		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 Cement: 2 coarse sand): 4 graded stone aggregate 20 mm nominal size.	1.031	Cum		

4	Disposal of building rubbish /similar unserviceable, dismantled or waste materials by mechanical Disposal of malba /means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved		8 Cum		
	Total				


 Assistant Engineer
 Municipal Corporation
 Mandi (H.P.)