JOB NO. -16

Bidders Name & Address ----------**Dated**----------

Assistant Engineer
Municipal Corporation
Mandi (H.P.)

Form-6

MUNICIPAL CORPORATION MANDI
NOTICE INVITING TENDER

1. Items rate tenders are hereby invited on behalf of the Commissioner Municipal corporation mandi for the work: **Restoration & repair to rain damage path (SH:- C/o protection wall) near H/o Smt. Pushpa Rai (H. No. 216/11) W. No. 13 MC Mandi**
2. The estimated Cost of Rs. **72774/-**
3. Contractor documents consisting of detail plans complete specifications. The scheduled of quantities of the various clause of work to be done and the set of conditions of contract to be complied with the persons whose tender may be accepted which will also be found printed in the form of tender. The tender form can be downloaded from the website www.municipalcorporationmandi.in well before date of opening of bid. Tender form cost on **Rs. 350** payment (Non refundable) through DD in favors of Commissioner Municipal Corporation Mandi
4. The site for the work can be inspected on any working day.
5. Tender which should always be placed in sealed covers with the name of work written on the envelop will be received by this office up to 12.00 A.M. and will be opened by him on his office on the same day at 12.30 P.M on **17-11-2026.**
6. Tender are to be on PWD from No. 7/8 and time allowed for carrying out of the work will be 2 month to be reckoned from the 15th days after the date of written orders to commence of work.
7. The contractors should quote in figures as well as in words the rate & amount tendered by him the amount for each item should be worked out and the requisite total given.
8. When a contractor sign a tender in any Indian language to the percentage above or below of the tenders amount in the case of P.W.D. from-7 and the total amount tendered in the case of PWD from-8 and scheduled also be written in the same language. In the case of illiterate contractors the rates or the amounts tendered should be attested by a witness.
9. Issue of tender form will be stopped 3 hours before the date 7 time fixed for opening the tenders.
10. Earnest money amounting to **Rs. 1500** (Unless exempted) must accompany each tenders in the shape of National Saving Certificate/Fixed deposit receipts in any Post Office and bank in HP duly pledged in the name of the Commissioner Municipal Corporation Mandi and each tender is to be in sealed cover subscribed tender for above work and addressed to the Commissioner Municipal Corporation Mandi
11. The tenders those contractors who do not deposit the earnest money in the prescribed manners will summarily be rejected.
12. The acceptance of the tender will rest with Municipal Corporation Mandi, who does not bind himself to accept the lowest tender and reserves to himself the authority to reject any or all of the tenders conditions are not fulfilled on are incomplete in any respect are liable to be rejection.
13. Canvassing in connection with tenders strictly prohibited and the tender by the contractor who resort of conversing will be rejection.
14. All rate shall quoted on the form of the tender alone.
15. Item rate tender containing percentage below above will be summarily rejected. However then a tenderer voluntarily offers rebate for payments within a stipulated period, this may be considered.
16. On acceptance of the tender the same of the accredited representative (s) of the contractor who would be responsible for taking instruction from the Engineer-in-charge shall be communicated to the Engineer.
17. Special care should be taken to write the rates in figures as well as in words and the amounts in figures only in such a way that interpolation is not possible. The total amount should be written both in figures and in words. In case figures, words (Rs.) should be written before the figures proceed and the words 'paisa')

SCHEDULE OF QUANTITY

Job No. 16
Estimate Cost: 72774.00
Earnest Money: 1500.00
Time Allowed: 2 month
Tender Form Cost: 350.00

Name of Bidder ----------Dated ----------

Assistant Engineer
Municipal Corporation
Mandi (H.P.)

Name of Work:- Restoration & repair to rain damage path (SUB-HEAD- C/O protection wall) near H/O Smt. Pushpa Rai (H.No. 216/11) W.No. 13 MC Mandi.

S. No.	Item of work	Qty.	Unit.	Rate (in figures)	Rates (In words)	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including	6.94	cum			
2	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts,struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills,fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	7.50	Cum			
3	Centering and shuttering including strutting, proppingetc. and removal of form for :Retaining walls, return walls, walls(any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc.	20.37	sqm			

4	Stone Boulder filling behind Retaining Wall	2.85	cum			
5	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 110mm dia PVC pipe extending through the full width of the structure with slope of 1(V) : 20(H) towards drawing face complete	7.00	No.s			
6	Providing & fixing Display board of Size 3' x 2' (minimum) indicating Name of work, Name of head, Estimated Cost, Date of Award, Date of start, Date of completion & Expenditure of work on site of work at prominent place.	1.00	each			
	Total					

Assistant Engineer
Municipal Corporation
Mandi (H.P.)