

## SCHEDUL OF QUANTITY ( NIQ)

Bidder Name & Address \_\_\_\_\_

Assistant Engineer  
Municipal Corporation  
Mandi (H.P.)

**Job No. 02**

Estimate Cost: 29484.00

Time Allowed: 2 month

Name of Work:- C/o underground Drain with repair to chamber near shop of dilu ram company in Ward No. 10 MC Mandi (H.P.).

| S. No. | Item of work                                                                                                                                                                                                                                                                                                                                                                | Qty. | Unit. | Rate (in figures) | Rates (In words) | Amount |
|--------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------|-------------------|------------------|--------|
| 1      | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, Including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. Ordinary rock | 3.45 | cum   |                   |                  |        |
| 2      | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering-All work upto plinth level- 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)                                                                                                                                               | 0.24 | cum   |                   |                  |        |
| 3      | Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :300 mm dia. R.C.C. pipe                                                                                                                         | 8.00 | Rmt   |                   |                  |        |
| 4      | Boulder filling dry hand packed tightly under floors                                                                                                                                                                                                                                                                                                                        | 0.90 | cum   |                   |                  |        |
| 5      | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering-All work upto plinth level- 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)                                                                                                                                               | 0.60 | cum   |                   |                  |        |
| 6      | Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in : Cement mortar 1:3 (1 cement : 3 coarse sand)                                                                                                                                                                                                  | 1.92 | sqm   |                   |                  |        |

|   |                                                                                                                                                                                                                                                                                          |       |    |  |  |  |
|---|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|----|--|--|--|
| 7 | Steel work welded in built up sections / framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In Gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. | 46.08 | Kg |  |  |  |
|   | <b>Total</b>                                                                                                                                                                                                                                                                             |       |    |  |  |  |

  
 Assistant Engineer  
 Municipal Corporation  
 Mandi (H.P.)